

Roscommon County Road Commission

Scott Eckstorm, Commissioner
James Porath, Commissioner
Justin Wykoff, Commissioner
Clint Stauffer, Commission
Brian Vaughn, Commissioner

820 E. West Branch Road
Prudenville, MI 48651

Roger Saxton, Manager
Phone:(989)366-0333
Fax:(989)366-0299
Website: www.roscommoncrc.com
E-mail: rcrc@roscommoncrc.com

NOTICE TO BIDDERS

The Roscommon County Road Commission will receive sealed bids until 2:00 p.m. on March 25, 2026. Bids will be opened for tabulation and review immediately thereafter. The bid will be awarded at the Roscommon County Road Commission's regularly scheduled board meeting on March 26, 2026 beginning at 7:00 p.m. Our office is located at 820 E. West Branch Road, Prudenville, MI 48651.

PAVEMENT MARKING, SPECIALTY MARKINGS AND THERMOPLASTIC SNOWMOBILE CROSSINGS

For any questions or to request bid specifications, please contact the Roscommon County Road Commission at the above address, by calling (989)-366-0333 ext 1007 or email dahlstromb@roscommoncrc.com.

Submit bids in sealed envelope that is clearly marked with the words "**2026 & 2027 PAVEMENT MARKING**" in the lower left corner.

The Roscommon County Road Commission reserves the right to reject any or all bids, to waive irregularities in any bid, to waive details in the specifications, and to accept the bid deemed to be in the best interest of Roscommon County. This is a **Two Year** bid. Bids may be extended for additional years with mutual agreement.

The Roscommon County Road Commission has adopted a Local Contractor Preference Policy. Visit 'Adopted Policies' at www.roscommoncrc.com for details and application form.

The Roscommon County Road Commission reserves the right to add or delete pavement marking segments or parts thereof at any time. Location maps will be available for pickup upon request.

ROSCOMMON COUNTY BOARD
OF ROAD COMMISSIONERS

Jim Porath, Chair
Brian Vaughn, Vice Chair
Justin Wykoff, Member
Clint Stauffer, Member
Scott Eckstorm, Member

ROSCOMMON COUNTY ROAD COMMISSION 2026 PAVEMENT MARKING LIST

Pavement Markings of Primary Roads:

To include center line and edge lines unless otherwise noted. Complete blank columns and submit with invoice for payment.

Road Name	Location	Notes	Yellow Center Line (Ft)	Yellow Painted (Ft)	White Edge Line (Ft)	White Painted (Ft)
CR 100	M-18 (Randys) north to CR 104		48,502		94,103	
CR 102	CR 100 to M-18	After Construction	8,942		29,716	
CR 104	Old 27 to CR 100	After Construction	29,459		52,825	
CR 104	Old 27 to Deadstream Rd		6,244		7,740	
CR 105	M-18 to Landfill Rd	Centerline Only	10,125		-	-
CR 107	Lake James Dr to M-55		4,074		12,882	
CR 300	M-55 to Old 27	After Construction	27,709		50,265	
CR 300	Old 27 to CR 100		58,511		74,108	
CR 301	CR 104 to N county line		18,104		35,766	
CR 303	M-55 to CR 300		19,891		25,882	
CR 304	M-55 to M-55		12,482		10,946	
CR 304	Old 27 to M-55		5,805		11,795	
CR 305	Old 27 to M-55		3,909		18,775	
CR 306	CR 400 to CR 304 (Heightview Dr)		18,367		35,580	
CR 400	Old 27 to M-18		32,815		72,180	
CR 400	Old 27 west to end of HMA		10,132		10,568	
CR 401	M-55 to M-55		35,170		34,123	
CR 401	Start of HMA to M-55	After Construction	20,168		35,931	
CR 402	Old 27 west to end of HMA	Centerline Only	4,396		-	-
Old 27	S county line to W AuSable Rd	After Construction	60,089		217,124	
		TOTAL	434,894		830,309	

Pavement Markings of Local Roads:

To include center line and edge lines unless otherwise noted. Complete blank columns and submit with invoice for payment.

Road Name	Location	Notes	Yellow Center Line (Ft)	Yellow Painted (Ft)	White Edge Line (Ft)	White Painted (Ft)
Main St (Denton)	M-55 to Silverwood Dr		4,507		4,236	
Silverwood Dr (Denton)	Main St to Lake James Dr		1,211		1,336	
Lake James Dr (Denton)	Main St to CR 107		25,400		24,702	
Springwood Dr (Denton)	M-55 to CR 107		20,460		19,726	
Nestel Rd (Denton)	CR 401 to Owens Dr	Centerline Only	3,520		-	-
Owens Dr (Denton)	Nestel Rd to M-55		643		4,990	
Grapevine Ave (Denton)	Apple Blossom to M-55	Centerline Only	356		-	-
Townline Rd (Denton/Roscommon)	Start of HMA to M-55		17,433		20,223	
Cherven Ln (Higgins)	North Central Dr to N county line	After Construction	600		4,760	
Lancewood Dr (Higgins)	M-18 to N county line	After Construction	6,380		6,274	
E Airport Rd (Richfield)	Old 76 to end of HMA	After Construction	5,710		11,417	
Towerhill Rd (Roscommon)	Start of HMA to M-55		15,997		37,408	
Nellsville Rd (Roscommon)	Start of HMA to M-55		13,364		15,322	
Nestel Rd (Roscommon)	CR 306 to Townline Rd		8,785		20,485	
Collingwood Blvd (Roscommon)	CR 305 to Stoneschool Rd		801		5,701	
West Shore Dr (Lake)	Old 27 to Old 27		29,394		39,086	
		TOTAL	154,561		215,666	

NOTES:

Desired Completion Date: This project is desired to be completed no later than September 30, 2026. If fall striping is required use price adjustment per section 811 of the Standard Specifications for Construction.

The edge lines shall be a single 4" line, where double edge lines are present only the inside line shall be painted

ROSCOMMON COUNTY ROAD COMMISSION 2027 PAVEMENT MARKING LIST

Pavement Markings of Primary Roads:

To include center line and edge lines unless otherwise noted. Complete blank columns and submit with invoice for payment.

Road Name	Location	Notes	Yellow Center Line (Ft)	Yellow Painted (Ft)	White Edge Line (Ft)	White Painted (Ft)
CR 100	CR 104 north to Marl Lake Entrance		6,873		4,828	
CR 100	Burdell Rd north to M-18 (Roscommon Post Office)		31,704		45,322	
CR 103	M-18 to N Higgins Lake Dr		34,855		81,620	
CR 103	M-18 to Old 76		8,440		26,779	
CR 106	Maplehurst Dr to CR 100		5,140		4,771	
CR 106	CR 100 to I-75 BL (W Federal Hwy)		5,172		12,363	
CR 200	CR 104 to Old 27 (Ironwood & Salem)	Stripe at 10' Lanes	66,184		93,836	
CR 201	Old 27 to CR 200		13,068		12,334	
CR 202	CR 104 to CR 200		6,905		16,940	
CR 300	S Long Point Dr to CR 100	After Construction	30,396		37,328	
CR 400	Gravel to Old 27	After Construction	10,132		10,568	
CR 400	CR 401 to M-18	After Construction	12,828		31,118	
CR 602	F-97 east to end of HMA	Centerline Only	1,364		-	-
CR 602	CR 603 to F-97		13,958		47,094	
CR 603	M-18 to F-97		19,109		39,994	
F-18	F-97 to E county line	After Construction	35,074		60,177	
F-28	F-97 to E county line		5,767		21,331	
F-97	S county line to Old 55		70,333		108,944	
F-97	Old 55 to Old 76		13,030		66,426	
F-97	Old 76 to N county line		23,848		98,750	
Old 76	Old 55 to South St		30,052		182,338	
		TOTAL	444,232		1,002,861	

Pavement Markings of Local Roads:

To include center line and edge lines unless otherwise noted. Complete blank columns and submit with invoice for payment.

Road Name	Location	Notes	Yellow Center Line (Ft)	Yellow Painted (Ft)	White Edge Line (Ft)	White Painted (Ft)
N Central Dr (Higgins)	Gerrish Twp Line to Roscommon Village Line		6,627		9,465	
N Central Dr (Gerrish)	I-75 BL (W Federal Hwy) to Higgins Twp Line		2,577		3,681	
Maplehurst Dr (Gerrish)	CR 103 to CR 100		5,506		9,884	
Burdell Rd (Gerrish)	CR 103 to CR 100		2,586		4,868	
Sunset Dr (Gerrish)	CR 103 to CR 101		6,872		10,451	
Long Point Dr (Lake)	CR 300 to CR 300		27,104		29,445	
W Higgins Lake Dr (Lyon)	CR 200 (Ironwood Rd) to N Higgins Lake Dr		9,198		12,293	
Flint Rd (Markey)	CR 104 to CR 300		7,948		32,112	
Ash St (Higgins/Richfield)	F-97 (AB) to Russel Lake Rd		315		2,509	
E Airport Rd (Richfield)	Old 76 to end of HMA		5,710		11,417	
W Airport Rd (Richfield)	Old 76 to Iroquois Trl.		3,219		10,102	
Madison St (Richfield)	Old 76 to F-97		1,470		1,307	
Central Dr (Richfield)	F-97 to end of HMA		3,965		17,210	
		TOTAL	83,097		154,744	

NOTES:

Desired Completion Date: This project is desired to be completed no later than September 30, 2027. If fall striping is required use price adjustment per section 811 of the Standard Specification for Construction.

The edge lines shall be a single 4" line, where double edge lines are present only the inside line shall be painted

ROSCOMMON COUNTY ROAD COMMISSION

Specifications for Pavement Marking

Description: Furnish and install retroreflective permanent pavement markings according to the current Michigan Manual of Uniform Traffic Control Devices. All markings, shapes, spacing and dimensions shall conform to the MDOT Pavement Marking Typical Plans unless specifically noted herein.

Supervision: All work shall be performed under the supervision of the Roscommon County Road Commission.

Construction & Materials: All Construction and Materials must meet the requirements of the current MDOT (Michigan Department of Transportation) Standard Specifications for Construction, MDOT Special Provisions, and RCRC Special Provision.

Maintaining Traffic and Safety: The contractor shall be responsible for maintaining traffic and shall protect painted lines until dry or cured to a no-pickup condition. All safety features and equipment required by law shall be maintained in good working condition by the contractor.

Insurance: Bidder shall provide Certificate of Insurance prior to commencing work. Certificate shall include: 1) Board of County Road Commissioners and Roscommon County Road Commission named as additional insured to all coverage, 2) General Liability \$1,000,000 each occurrence, 3) Automotive Liability-\$1,000,000 each occurrence, and 4) Worker's compensation - statutory limits.

Method of Payment: All paint, beads, and application, whether intermittent or solid, shall be measured and paid for as feet, square feet or each as marked. Contractor shall fill out the blank columns on the attached pavement marking list when submitting for payment. Segments on the pavement marking list must be painted in their entirety prior to submitting for payment.

Quantity: The bid sheet reflects the RCRC's best estimate of the required amount of work at this time. "After Construction" means there is a project on that road and will not be ready to stripe until after the work is completed. A second round list will be send out when work has been completed if the roads without the "After Construction" note has already been striped. "After Construction" notes may change as they are based on road plans at the time of bid. The Roscommon County Road Commission reserves the right to add or delete quantities from the bid, deemed to be in the best interest of the Roscommon County Road Commission.

ROSCOMMON COUNTY ROAD COMMISSION 2026 PAVEMENT MARKING BID SHEET

	<u>Unit Price</u>	<u>Total</u>
Total Center Line Marking 2026 (589,455 Ft)	\$ _____ Ft	\$ _____
Total Edge Line Marking 2026 (1,045,975 Ft)	\$ _____ Ft	\$ _____
Pavt Mrkg, Polyurea, 6" Crosswalks 2026 (As needed Ft)	\$ _____ Ft	\$ _____
Pavt Mrkg, Polyurea, 12" Crosswalks 2026 (As needed Ft)	\$ _____ Ft	\$ _____
Pavt Mrkg, Polyurea, Left Arrow 2026 (As needed Ea)	\$ _____ Ea	\$ _____
Pavt Mrkg, Polyurea, Thru Arrow 2026 (As needed Ea)	\$ _____ Ea	\$ _____
Pavt Mrkg, Polyurea, Right Arrow 2026 (As needed Ea)	\$ _____ Ea	\$ _____
Pavt Mrkg, Polyurea, Left/Thru Combo Arrow 2026 (As needed Ea)	\$ _____ Ea	\$ _____
Pavt Mrkg, Polyurea, Right/Thru Combo Arrow 2026 (As needed Ea)	\$ _____ Ea	\$ _____
Pavt Mrkg, Polyurea, Railroad Grade Crossing Marking 2026 (As needed Ea)	\$ _____ Ea	\$ _____
Pavt Mrkg, Polyurea, School Symbols 2026 (As needed Ea)	\$ _____ Ea	\$ _____
Pavt Mrkg, Polyurea, Stop Bars, 24" 2026 (As needed Ft)	\$ _____ Ft	\$ _____
Rem Spec Mrkg 2026 (As needed Sft)	\$ _____ Sft	\$ _____
Thermoplastic Snowmobile Crossing 2026 (As needed Sft)	\$ _____ Sft	\$ _____

Total Bid \$ _____

Company Name

Telephone Number

Mailing Address

Fax Number

City, State, Zip

Date

Authorized Company Representative's Signature

Email

ROSCOMMON COUNTY ROAD COMMISSION 2027 PAVEMENT MARKING BID SHEET

	<u>Unit Price</u>	<u>Total</u>
Total Center Line Marking 2027 (527,329 Ft)	\$ _____ Ft	\$ _____
Total Edge Line Marking 2027 (1,157,605 Ft)	\$ _____ Ft	\$ _____
Pavt Mrkg, Polyurea, 6" Crosswalks 2027 As needed Ft)	\$ _____ Ft	\$ _____
Pavt Mrkg, Polyurea, 12" Crosswalks 2027 (As needed Ft)	\$ _____ Ft	\$ _____
Pavt Mrkg, Polyurea, Left Arrow 2027 (As needed Ea)	\$ _____ Ea	\$ _____
Pavt Mrkg, Polyurea, Thru Arrow 2027 (As needed Ea)	\$ _____ Ea	\$ _____
Pavt Mrkg, Polyurea, Right Arrow 2027 (As needed Ea)	\$ _____ Ea	\$ _____
Pavt Mrkg, Polyurea, Left/Thru Combo Arrow 2027 (As needed Ea)	\$ _____ Ea	\$ _____
Pavt Mrkg, Polyurea, Right/Thru Combo Arrow 2027 (As needed Ea)	\$ _____ Ea	\$ _____
Pavt Mrkg, Polyurea, Railroad Grade Crossing Marking 2027 (As needed Ea)	\$ _____ Ea	\$ _____
Pavt Mrkg, Polyurea, School Symbols 2027 (As needed Ea)	\$ _____ Ea	\$ _____
Pavt Mrkg, Polyurea, Stop Bars, 24" 2027 (As needed Ft)	\$ _____ Ft	\$ _____
Rem Spec Mrkg 2027 (As needed Sft)	\$ _____ Sft	\$ _____
Thermoplastic Snowmobile Crossing 2027 (As needed Sft)	\$ _____ Sft	\$ _____

Total Bid \$ _____

Company Name

Telephone Number

Mailing Address

Fax Number

City, State, Zip

Date

Authorized Company Representative's Signature

Email